

**Borough of Crafton
100 Stotz Avenue
Pittsburgh, PA 15205**

PERMIT APPLICATION

Application Type: (Check All That Apply) 1. Street Opening & Excavation 2. Curb Cut & Driveway Construction
3. Sidewalk Construction & Repair 4. Unimproved Areas in Public R/W

DATE: _____

Applicant Name: _____

Applicant Address: _____

Phone/Fax #/E-Mail Address: _____ / _____ / _____

Person or Contractor Performing the Work (if Different than Applicant)

Contact Name: _____

Phone/Fax #/E-Mail Address: _____ / _____ / _____

Description of Work: Include specific details for the requested work including; dimensions, disturbed area, street map & nearest street address. (Attach additional sheets as needed to describe the proposed work)

Emergency Work: Yes No

Plans & Attachments: Yes No

Location of Work: (Check All That Apply)

- Center of Road (Restoration shall be full width of roadway pavement)
- Driving Lane (Restoration shall be full width of driving lane pavement)
- Curb and/or Edge of Road (Restoration shall be full width of driving lane pavement)
- Sidewalk (Restoration shall be portion of sidewalk removed)
- Driveway (Restoration shall be portion of driveway disturbed)
- Public Right-of-Way (Restoration shall be to replace in-kind)

Notes:

1. Restoration of Pavement length shall be five feet beyond extent of excavated area to include keyways and joint sealing.
2. Restoration of all excavated, removed or disturbed areas shall be per Borough Specifications.
3. Final Inspection and acceptance of the Restoration shall be at the discretion of the Borough Engineer.

Composition of Surfaces in Excavation Areas -

- 1. Concrete
- 2. Asphalt
- 3. Brick
- 4. Lawn
- 5. Other: _____

Start Date: _____ Completion Date: _____

PA One Call Serial Number: _____

Certificate of Insurance - Workers Compensation and Liability Coverage Required (Furnish Proof of Insurance)

OFFICIAL USE ONLY

APPLICATION NO. : _____ DATE: _____ / _____ / _____

**Borough of Crafton
100 Stotz Avenue
Pittsburgh, PA 15205**

FEE CALCULATION

Application Fee:

- | | | |
|---------------------------------------|------------------------------|-----------------------|
| 1. Street Opening & Excavation - | \$1 per sq. ft. of Opening | _____ S.F. = \$ _____ |
| Residential Fee | \$100.00 Minimum | |
| Non-Residential Fee | \$500.00 Minimum | |
| 2. Curb Cut & Driveway Construction - | \$1 per lin. ft. Curb | _____ L.F. = \$ _____ |
| | \$1 sq. ft. Driveway | _____ S.F. = \$ _____ |
| Residential Fee | \$ 75.00 Minimum | |
| Non-Residential Fee | \$375.00 Minimum | |
| 3. Sidewalk Construction & Repair - | \$1 per lin. ft. of Sidewalk | _____ L.F. = \$ _____ |
| Residential Fee | \$ 50.00 Minimum | |
| Non-Residential Fee | \$200.00 Minimum | |
| 4. Public Right-of-Way Disturbances - | Flat Fee | = \$ _____ |
| Residential Fee | \$ 50.00 Minimum | |
| Non-Residential Fee | \$200.00 Minimum | |
| TOTAL Application Fee | | = \$ _____ |

Note: The Borough, at its discretion, may require the above activities be reviewed and/or inspected by the Borough Engineer or other consultants. The Applicant is responsible for all costs associated with these reviews and/or inspections. Refer to Section 18, Streets, Driveways and Sidewalks, the general schedule of fees, costs, charges and expenses.

Restoration Guarantee as Certified Check or Cashier's Check

CALCULATION:

- | | |
|--|---------|
| 1. _____ Sq. Ft. of Pavement Replacement @ \$20/S.F. | = _____ |
| 2. _____ Sq. Ft. of Driveway Replacement @ \$15/S.F. | = _____ |
| 3. _____ Sq. Ft. of Driveway Replacement @ \$10/S.F. | = _____ |
| 4. _____ Sq. Ft. of Lawn Replacement @ \$5/S.F. | = _____ |
| TOTAL Restoration Guarantee | = _____ |

I, (Applicant/Authorized Representative) hereby agree to save the Borough, its Officers, Engineer, Police and Agents harmless from any and all costs, damages and liabilities which may accrue or be claimed to accrue by reason of such work performed under this Permit:

BY: _____ (Print Name) _____ (Signature)


OFFICIAL USE ONLY

APPLICATION NO. : _____ DATE: _____ / _____ / _____

ISSUED BY: _____

FEE PAID: _____ CHECK NO. _____ OTHER: _____


Restoration Guarantee: \$ _____ CHECK NO. _____ OTHER: _____



BRICK / BELGIAN BLOCK PAVING DETAIL


CRAFTON BOROUGH STANDARD DETAILS

9.18



SPECIFICATIONS FOR REPAIRING STREET OPENINGS

1. THE TEMPORARY BACKFILL WILL BE COMPLETELY REMOVED FROM THE OPENING TO THE EXISTING 2A AGGREGATE BASE WHICH SHALL BE FULLY COMPACTED. THE EDGES OF THE OPENING WILL BE SAW CUT.
2. THE OPENING WILL BE BACKFILLED WITH A 2A LIMESTONE COMPACTED TO 7 1/2" BELOW THE TOP OF THE EXISTING PAVEMENT. THE OPENING SHALL THEN BE BACKFILLED WITH 6" OF BITUMINOUS CONCRETE BASE COURSE.
3. THE STREET SHALL BE MILLED 1-1/2" THE FULL WIDTH OF THE STREET AND THE LENGTH DETERMINED BY THE AUTHORIZED BOROUGH REPRESENTATIVE, WITH 60 LINEAL FEET GENERALLY BEING THE MINIMUM.
4. PRIOR TO THE RESURFACING OF THE STREET, A PETROMAT FABRIC WILL BE PLACED OVER THE BITUMINOUS CONCRETE BASE COURSE.
5. 1-1/2" 9.5mm WEARING WILL BE PLACED OVER THE ENTIRE SURFACE FROM CURB TO CURB AND THE GUTTERS AND EDGES SEALED WITH A 6" BITUMINOUS SEAL OF PG 64-22.
6. IF THE STREET OPENING OCCURS IN A BRICK OR BLOCK STREET, REFER TO CRAFTON CONSTRUCTION STANDARD NUMBER 9.18 FOR REPAIR REQUIREMENTS.
7. THE REPAIR REQUIREMENTS SHOWN ON THIS DETAIL SHALL BE APPLICABLE FOR ALL NEWLY PAVED ROADS (WITHIN 5 YEARS). SEE CONSTRUCTION STANDARD 9.24 FOR REPAIR REQUIREMENTS FOR ROADS THAT WERE PAVED MORE THAN FIVE (5) YEARS AGO.




PLAN VIEW

NEW BITUMINOUS STREET OPENING REPAIR DETAIL


CRAFTON BOROUGH STANDARD DETAILS

9.21



NOTE:
 COUNTY & STATE SPECIFICATIONS
 SHALL SUPERCEDE THIS DETAIL IN
 THEIR PAVEMENTS.

**DETAIL OF TRENCH REPAVING
 FOR BITUMINOUS STREETS**




NOTES:
 SURFACE TO BE TREATED WITH A CURING AND
 SEALING COMPOUND COUNTY & STATE
 SPECIFICATIONS SHALL SUPERCEDE THIS
 DETAIL IN THEIR PAVEMENTS.


**DETAIL OF TRENCH REPAVING
 FOR CONCRETE STREETS**

NOTE:
 THIS CONSTRUCTION STANDARD SHALL BE USED FOR ALL
 BOROUGH STREETS NOT NEWLY RESURFACED WITHIN 5 YEARS.

UTILITY TRENCH REPAIR FOR BOROUGH STREETS




**DETAIL OF TRENCH REPAVING
FOR BITUMINOUS STREETS**



**DETAIL OF TRENCH REPAVING
FOR CONCRETE STREETS**


NOTE:
THIS CONSTRUCTION STANDARD SHALL BE USED FOR ALL
BOROUGH STREETS NOT NEWLY RESURFACED WITHIN 5 YEARS.

UTILITY TRENCH REPAIR FOR BOROUGH STREETS



SPECIFICATIONS FOR REPAIRING STREET OPENINGS

1. THE TEMPORARY BACKFILL WILL BE COMPLETELY REMOVED FROM THE OPENING TO THE EXISTING 2A AGGREGATE BASE WHICH SHALL BE FULLY COMPACTED. THE EDGES OF THE OPENING WILL BE SAW CUT.
2. THE OPENING WILL BE BACKFILLED WITH A 2A LIMESTONE COMPACTED TO 7 1/2" BELOW THE TOP OF THE EXISTING PAVEMENT. THE OPENING SHALL THEN BE BACKFILLED WITH 6" OF BITUMINOUS CONCRETE BASE COURSE.
3. THE STREET SHALL BE MILLED 1-1/2" THE FULL WIDTH OF THE STREET AND THE LENGTH DETERMINED BY THE AUTHORIZED BOROUGH REPRESENTATIVE, WITH 60 LINEAL FEET GENERALLY BEING THE MINIMUM.
4. PRIOR TO THE RESURFACING OF THE STREET, A PETROMAT FABRIC WILL BE PLACED OVER THE BITUMINOUS CONCRETE BASE COURSE.
5. 1-1/2" 9.5mm WEARING WILL BE PLACED OVER THE ENTIRE SURFACE FROM CURB TO CURB AND THE GUTTERS AND EDGES SEALED WITH A 6" BITUMINOUS SEAL OF PG 64-22.
6. IF THE STREET OPENING OCCURS IN A BRICK OR BLOCK STREET, REFER TO CRAFTON CONSTRUCTION STANDARD NUMBER 9.18 FOR REPAIR REQUIREMENTS.
7. THE REPAIR REQUIREMENTS SHOWN ON THIS DETAIL SHALL BE APPLICABLE FOR ALL NEWLY PAVED ROADS (WITHIN 5 YEARS). SEE CONSTRUCTION STANDARD 9.24 FOR REPAIR REQUIREMENTS FOR ROADS THAT WERE PAVED MORE THAN FIVE (5) YEARS AGO.




PLAN VIEW

NEW BITUMINOUS STREET OPENING REPAIR DETAIL

CRAFTON BOROUGH STANDARD DETAILS

9.21



BRICK / BELGIAN BLOCK PAVING DETAIL

CRAFTON BOROUGH STANDARD DETAILS

9.18

Borough of Crafton, PA
Friday, March 18, 2016

Chapter 177. Sewers and Sewage Disposal

Article II. Sewer Connections

§ 177-2. Connection to sanitary sewers.

- A. All buildings and/or uses located in the Borough of Crafton shall be connected to the Borough's sanitary sewer system. All sewer connections shall comply with the provisions of this chapter, Code or other ordinance of the Borough, specifications of the Borough Engineer, and all applicable provisions of the Allegheny County Plumbing Code and the rules and regulations of the Allegheny County Health Department.
- B. No more than one building shall be connected to a sewer through any one connection without the consent of Borough Council.

§ 177-3. Connecting storm or surface drainage facilities to sanitary sewer prohibited.

[Amended 4-26-2006 by Ord. No. 1576]

After the effective date of this article, no person shall connect any roof leaders, roof drains, downspouts, gutters, parking lot drains, driveway drains, interior or exterior sumps, exterior foundation drains, drains or other sources of surface stormwater runoff and groundwater to any sanitary sewer.

§ 177-4. Permit and fees for sewer connections.

Any persons desiring to connect to the Borough sewer system shall apply to the Borough Manager for a sewer connection permit. The Manager shall issue the permit following a review of the application to assure all other necessary Borough, county, state and federal approvals or permits have been obtained and upon payment of a fee, in an amount as established from time to time by resolution of Borough Council.

§ 177-5. Street openings and work and repairs to Borough streets.

- A. No person shall open any public street in the Borough for any sewer-related work without a street opening permit in accordance with Chapter 193, Streets and Sidewalks.
- B. All work performed in connecting any property with a public sewer shall be at the expense of the person making the connection. All work and repairs to street and sidewalks shall be done in accordance with Borough specifications and under the supervision of the Borough Manager or

other designated Borough employee. Any work within the right-of-way of a public street shall be performed by a registered master plumber and comply with the requirements of the Allegheny County Plumbing Code.

§ 177-6. Violations and penalties.

- A. Any person, firm or corporation who violates a provision of this chapter/article, or who fails to comply therewith, or with any of the requirements thereof, shall be, upon conviction thereof, sentenced to pay a fine of not less than \$500 nor more than \$5,000 for each violation, plus costs, and, in default of payment of said fine and costs, to imprisonment to the extent permitted by law for the punishment of summary offenses.
- B. A separate offense shall arise for each day or portion thereof in which a violation is found to exist or for each section of this article found to have been violated. All fines and penalties for the violation of this article shall be paid to the Borough Treasurer.
- C. The Borough may also commence appropriate actions in equity, at law or other to prevent, restrain, correct, enjoin, or abate violations of this article.

§ 177-6.1. Maintenance responsibility.

[Added 4-26-2006 by Ord. No. 1576]

- A. Owners of property within the Borough shall be responsible for the maintenance of sewer lines inside a building and on the owner's property and for the maintenance of sewer lateral lines extending from a building or private property to the main sewer lines.
- B. The Borough shall not be responsible for the maintenance of sewer lines inside a building or the maintenance of sewer lateral lines extending from a building or private property to the main sewer lines, or for damages caused by sewage or water escaping therefrom, or for lines or fixtures on private property.